



Republic of the Philippines
Department of Agriculture
PHILIPPINE FIBER INDUSTRY DEVELOPMENT AUTHORITY
3/F DA-PCAF Bldg., Department of Agriculture, Elliptical Rd., Diliman, Quezon City

REQUEST FOR QUOTATION

The Philippine Fiber Industry Development Authority (PhilFIDA), thru its Bids and Awards Committee (BAC) invites all manufacturers, suppliers and distributors to send their sealed bids/quotations, within seven (7) days from publication hereof, for the supply/delivery of the items enumerated below:

CONTRACTS	Item No.	Qty.	Unit	Description of Items	Approved Budget(PhP)	Place of Delivery
PR NO: 16-03-248				Supply of Materials and Labor for the Painting of Engineering Workshop and Covered Work Area at PhilFIDA-Fiber Processing and Utilization Laboratory, BAI Compound, Visayas Ave., Diliman, Quezon City Note: <ul style="list-style-type: none">- Duration: Ten (10) days- With six (6) months warranty on painting, materials and services- See attached Scope of Works- See attached Detailed Scope of Works	134,934.64	<i>FiberUtilization & Technology Division BAI Compound, Visayas Ave., Quezon City</i>
				TOTAL	134,934.64	

Interested bidders must be included in the registry of manufacturers/suppliers/distributors in the PhilGEPS. **PRICE QUOTATIONS SHALL BE IN ORIGINAL COPY, DULY SIGNED AND SUBMITTED IN A SEALED ENVELOPE.** Please note that we do not accept quotations through email or fax. Information relating to examination, evaluation and comparison of price quotations shall be kept confidential.

Deadline for submission of quotation : 4 April 2016, PhilFIDA, 3/F DA-PCAF Bldg., Department of Agriculture, Elliptical Rd., Diliman, Quezon City.

Please submit your sealed bid / quotation only to the PhilFIDA-BAC Secretariat, addressed to Mr. Victor Y. Romano

For inquiries, please call BAC Secretariat at Telephone No. 2732474 to 78 / 9288756 to 65 local 2653.


JOSE L. CATALLA
BAC, Chairperson



"Halamang Hible: Yaman ng Bayan, Biyaya ng Kalikasan"

PROJECT : PAINTING OF ENGINEERING WORKSHOP AND COVERED
 WORK AREA AT PhilFIDA-FPUL
 OWNER : PHILIPPINE FIBER INDUSTRY DEVELOPMENT AUTHORITY
 LOCATION : BAI COMPOUND, VISAYAS AVENUE, DILIMAN, QUEZON CITY
 SUBJECT : AGENCY ESTIMATE
 DATE : 9-Mar-16

ITEM	SCOPE OF WORKS	QTY	UNIT	UNIT COST	TOTAL COST
1.0	Supply and Material				
	Flooring, 185.19 square-meter				
	-Eposeal Clear	7.00	gal	1,150.00	8,050.00
	-Epopatch with Hardener, Full Putty	7.00	gal	2,150.00	15,050.00
	-Acreeex, two (2) coats, Gray	15.00	gal	1,150.00	17,250.00
	Flooring Lines, 5.0 square-meter				
	-Eposeal Clear	0.25	gal	1,150.00	287.50
	-Acreeex, two (2) coats, Yellow	0.25	gal	1,150.00	287.50
	Interior Walls and Columns, 134.03 square-meter				
	-Concrete Nuetralizer	0.50	gal	470.00	235.00
	-Acrylic Concrete Primer and Sealer	8.00	gal	500.00	4,000.00
	-Lattex Putty, Spot Putty	3.00	gal	315.00	945.00
	-Megacryl Latex Flat, two (2) coats, Light Yellow	9.00	gal	695.00	6,255.00
	-Megacryl Latex Flat, two (2) coats, Red Passion	0.25	gal	945.00	236.25
	-Megacryl Latex Flat, two (2) coats, Gold Sunset	0.25	gal	695.00	173.75
	Exterior Walls, 28.48 square-meter				
	-Concrete Nuetralizer	0.25	gal	470.00	117.50
	-Acrylic Concrete Primer and Sealer	2.00	gal	500.00	1,000.00
	-Lattex Putty, Spot Putty	1.00	gal	315.00	315.00
	-Megacryl Latex Flat, two (2) coats, Gold Sunset	2.00	gal	695.00	1,390.00
	Interior Ceiling, 165.11 square-meter				
	-Metal Primer-Red Oxide	6.00	gal	420.00	2,520.00
	-Gloss It-Quick Drying Enamel, two (2) coats, White	11.00	gal	645.00	7,095.00
	Exterior Ceiling, 17.90 square-meter				
	-Concrete Nuetralizer	0.25	gal	470.00	117.50
	-Acrylic Concrete Primer and Sealer	2.00	gal	500.00	1,000.00
	-Lattex Putty, Spot Putty	1.00	gal	315.00	315.00
	-Megacryl Latex Flat, two (2) coats, Light Gray	2.00	gal	695.00	1,390.00
	Faschia Board, 1.81 square-meter				
	-Concrete Nuetralizer	0.15	gal	470.00	70.50
	-Acrylic Concrete Primer and Sealer	0.20	gal	500.00	100.00
	-Lattex Putty, Spot Putty	0.15	gal	315.00	47.25
	-Megacryl Latex Flat, two (2) coats, Dark Gray	0.25	gal	695.00	173.75

Painting Tools and Consumables

Paint roller, 9"	7.00	pc	65.00	455.00
Paint roller, 7"	6.00	pc	55.00	330.00
Paint roller, 4"	6.00	pc	45.00	270.00
Roller tray (for 9" roller)	4.00	pc	80.00	320.00
Roller tray (for 7" roller)	4.00	pc	120.00	480.00
Roller tray (for 4" roller)	5.00	pc	120.00	600.00
Paint brush, 3"	5.00	pc	75.00	375.00
Paint brush, 2"	3.00	pc	65.00	195.00
Paint brush, 1½"	3.00	pc	60.00	180.00
Paint brush, 1"	3.00	pc	30.00	90.00
Sand paper	50.00	pc	15.00	750.00
Rugs	2.00	kg	40.00	80.00
Masking Tape, 2"W	2.00	pc	20.00	40.00
Metal Scraper	2.00	pc	50.00	100.00
Hand Gloves, Cotton	5.00	pc	30.00	150.00
Surgical Mask	10.00	pc	30.00	300.00
Container, Pail, Medium Size	3.00	pc	50.00	150.00
Paint Thinner	4.00	bottle	35.00	140.00
Putty plate	5.00	pc	25.00	125.00
Sub-total				73,551.50


2.0 Labor is forty percent (40%) of the total supply and material cost

- Conduct of actual site verification on the areas for painting including the paint's colors on what the customer wants and etc.
- Preparation of surfaces of walls, ceiling, columns, fascia before painting
- For floor's painting, provide sufficient and with good quality of the following materials;eposeal clear, epopatch with hardener (full putty) and Acreex (2 coats)
- For painting of concrete walls, ceiling, columns, fascias and etc., provide sufficient and with good quality of the following materials; concrete nuetralizer, acrylic concrete primer and sealer, latex putty and megacryl latex flat (2 coats)
- For painting of metal ceiling, provide sufficient and with good quality of the following materials; primer red oxide and gloss it-quick drying enamel (2 coats)
- Cleaning of project site and disposal of waste
- Provision of six (6) months warranty of material and services

Sub-total		29,420.60
Total Material Costs	P	73,551.50
Total Labor Cost		29,420.60


Total Direct Cost	102,972.10
Total Indirect Cost (17%)	17,505.26
Total Taxes (12 %)	14,457.28
Total Contract Cost	P 134,934.64

Prepared by:


 RAMIL B. BARCELONA
 Engineer III


 ROMEO P. DE VERA
 FDO-II

Check and reviewed by:


 IRMA B. RODIS
 Engineer II, Agricultural Engineer

Recommending Approval:


 REMEDIOS V. ABGONA, PhD
 Chief, FUTD

Approved:


 DR. CLARITO M. BARRON, CESO IV
 OIC, Executive Director

Project: Painting of Engineering Workshop and Covered Work Area at PhilFIDA-Fiber
Processing and Utilization Laboratory
Owner: Philippine Fiber Industry Development Authority (PhilFIDA)
Location: BAI Compound, Visayas Avenue, Diliman, Quezon City
Budget: PhP 134, 934.64 only
Duration: Ten (10) days


DETAILED SCOPE OF WORKS

1. Conduct of actual site verification on the areas for painting including the right colors on what the customer wants and etc..
2. For floor's painting (including yellow safety lines), provide sufficient and with good quality of the following materials; eposeal clear, epatch with hardener (full putty) and Acreex (2 coats).
3. For painting of concrete walls, ceiling, columns, fascias and etc., provide sufficient and with good quality of the following materials; concrete neutralizer, acrylic concrete primer and sealer, latex putty and megacryl latex flat (2 coats).
4. For painting of metal ceiling, provide sufficient and with good quality of the following materials; primer red oxide and gloss it-quick drying enamel (2 coats).
5. Cleaning of project site and disposal of waste.
6. Provision of six (6) months warranty on painting materials and services.

Prepared by:


RAMIL B. BARCELONA
Engineer III

Recommending Approval:


REMEDIOS V. ABGONA, PhD
Chief, FUTD

Approved:


DR. CLARITO M. BARRON, CESO IV
OIC, Executive Director