Name of Project : **COMPLETION OF WORKS OF 2-STOREY BIOTECH LABORATORY BUILDING**
Project Owner : **Philippine Fiber Industry Development Authority**
Location : **PhilFIDA, BAI Compound, Visayas Avenue, Diliman, Quezon City**

DETAILED QUANTITY & COST ESTIMATES

LINE NO.	ITEM DESCRIPTION	UNIT	QTY	MATERIALS COST		LABOR COST		LINE TOTAL
				UNIT	TOTAL	UNIT	TOTAL	
1.0	**TILE WORKS**							
	Floor Topping 5" = 15 m^3							
	sand	m^3	15.00					
	cement	bags	200.00					
	Synthetic granite tiles, 60 cm x 60 cm	pcs	550.00					
	Tile adhesive, heavy duty, 25 kg/bag	bags	30.00					
	Tile grout, 2 kg/bag, ABC or approved equal	bags	6.00					
	Stair (Ground Floor to Second Floor)							
	stair nosing	pcs	14.00					
	Unglazed ceramic tiles, 30 cm x 60 cm	pcs	95.00					
	cement	bags	15.00					
	sand	m^3	1.00					
	Tile adhesive, heavy duty, 25 kg/bag	bags	5.00					
	Tile grout, 2 kg/bag, ABC or approved equal	bags	3.00					
					TOTAL DIRECT COST (PhP)			
					CONTINGENCY/OVERHEAD/MARK-UP (PhP)			
					OH/MARK-UP (PhP)			
					VAT (PhP)			
					TOTAL PROJECT COST (PhP)			
	TOTAL							

Prepared by:

Signature and Name of Supplier

Name of Company