

PROJECT : Refurbishment of area for Dynamic Spinning Machine (DSM)
 OWNER : PHILIPPINE FIBER INDUSTRY DEVELOPMENT AUTHORITY
 LOCATION : BAI. COMPOUND, VISAYAS AVENUE, VASRA, QUEZON CITY
 DATE : JULY 12, 2019

BILL OF MATERIALS

PARTICULARS		QUANTITY	UNIT	UNIT PRICE	AMOUNT
I. Enclosure					
	KD 2 x 4 x 10	15	pcs		
	KD 1 x 1 x 8	40	pcs		
	KD 2 x 6 x 8	3	pcs		
	KD 1 x 6 x 8	7	pcs		
	KD 1 x 6 x 10	8	pcs		
	Baseboard 1 x 6 x 8	4	pcs		
	Marine Plywood # 1/2"	3	pcs		
	Aluminum Door Tracks w/ 1 pair hanger	1	pcs		
	Door Lock & handle	1	set		
	Clear Glass # 6mm	107	sq.ft		
	Common Nail, assorted	1	lot		
II. CEILING WORKS					
	Furring Channel	6	pcs		
	Carrying Channel	1	pcs		
	Wall Angle	4	pcs		
	Furring Clip	10	pcs		
	Hardiflex 1/4 x 4 x8	2	box		
	Blind Rivets 1/8 x 1/2	1	pcs		
	Drill Bit # 1/8 (Dormer)	2	pcs		
	Masonry Drill Bit 5/32	1	pcs		
III. MASONRY WORKS					
	Tiles # 12 x 12	190	pcs		
	Floor Tiles # 60 x 60	20	pcs		
	Tile Trim PVC	13	pcs		
	Tile Adhesive	10	bag		
	Tile Grout White	3	bag		
	Cement	6	bag		
	W-Sand	1	cu.m		
	CHB 4"	40	pcs		
	Steel bar 10mm	2	pcs		
	Skim Coat	1	bag		
	Stainless Sink w/ faucet 43 x 53	1	set		
IV. ELECTRICAL WORKS					
	Panel Box (8branches)	1	pcs		
	30Amp Circuit Breaker (Plug In)	3	pcs		
	60Amp Circuit Breaker (Plug In)	1	pcs		
	20Amp Circuit Breaker (Plug In)	1	pcs		
	15Amp Circuit Breaker (Plug In)	1	pcs		
	Stranded wire, THHN 3.5 Black	1	box		
	Stranded wire, THHN 2.0 Black	1	box		
	Stranded wire, THHN 8.0	100	m		
	3/4 Neltex Powerline	20	pcs		
	1/2 Neltex Powerline	20	pcs		
	3/4 Euroflex	20	m		

PARTICULARS		QUANTITY	UNIT	UNIT PRICE	AMOUNT
	1/2 Euroflex	20	m		
	2 Gang Plate Outlet	8	pcs		
	1 Gang Plate Outlet	11	pcs		
	Convenience Outlet	12	pcs		
	2 Gang Plate Switch	2	pcs		
	1Gang Plate Switch	2	pcs		
	1 way Switch	6	pcs		
	Electrical Tape 10m Black	10	pcs		
V. ROOFING WORKS					
	Pre Painted Corrugated Roof (Baguio Green) 0.5 x 1 x 2.44 m	11	pcs		
	Ridge Roll # 18	4	pcs		
	End Flashign # 18	2	pcs		
	Tekscrew # 2	100	pcs		
	Welding Rod 6013	1	kg		
	Silicon Sealant Clear	3	pcs		
VI. PAINTING WORKS					
	Flat Latex 701	2	gal		
	Semi gloss Latex 715	2	gal		
	Polituff	2	liter		
	Epoxy Primer (White or Grey)	2	liter		
	Patching Compound	1	kg		
	Lac spot putty	1	gal		
	Lacquer Thinner	3	bottle		
	Sand Paper # 100	5	pcs		
	Sand Paper # 120	5	pcs		
	Sand Paper # 240	5	pcs		
	Paint roller #7	1	pcs		
	Baby Roller (Cotton)	1	pcs		
	Baby Roller (foam)	1	pcs		
	Stikwel	2	pcs		
	Paint Brush #2"	2	pcs		
	Paint Brush #1"	2	pair		
	Paleta	1	pcs		
	spatula	1	pcs		

Prepared by:

Signature over printed name

Name of company: _____

Date signed: _____