

PROJECT : IMPROVMENTS OF CHEMICAL AND WET LAB. OF FPUL
 OWNER : PHILIPPINE FIBER INDUSTRY DEVELOPMENT AUTHORITY
 LOCATION : BAI. COMPOUND, VISAYAS AVENUE, VASRA, QUEZON CITY

BILL OF MATERIALS

PARTICULARS		QUANTITY	UNIT	UNIT PRICE, P	AMOUNT, P
I. SITE/AREA CLEARING/REMOVAL OF EXSISTING OBSTRUCTION		1	lot		
II. TEMP. CONSTRUCTION AREA ENCLOSURE		1	lot		
III. RESTORATION WORKS					
	Portland cement	8	bags		
	Sand	2	m ³		
	Floor Tiles, 30x30cm (chemical lab)	40	pcs		
	Wall Tiles, 30x30cm (chemical lab)	20	pcs		
	Floor Tiles, 60x60cm (Wet lab)	10	pcs		
	Wall Tiles, 30x30cm (Wet lab)	15	pcs		
	Tile grout	3	bags		
	Tile adhesive	3	bags		
	Assorted paints and putty	1	lot		
	Paint roller	1	pcs		
	Paint brush, 2"	2	pcs		
	Rags	3	kgs		
	Sand paper	20	pcs		
	GI # 16 Tie wire	3	kgs		
	Concrete nail, 2"	15	pcs		
IV. PLUMBING WORKS					
	PVC pipes, 3"dia. Orange	5	pcs		
	PVC pipes, 2"dia. Orange	2	pcs		
	Ppr pipes, 1" dia.	4	pcs		
	Assorted pipe fittings	1	lot		
	Solvent cement	3	can		
	Floor drain, S/S, 4X4"	3	pcs		
	Teflon tape	3	pcs		
V. HARDWARES					
	Shower head, stainless steel, rectangular, 10"X10", high quality, with accessories	2	pcs		
	Shower curtain railings, stainless steel, curved	2	pcs		
	Shower curtain, waterproof, pvc, clear, high quality	2	set		
	Shower knob, stainless steel, 1", high quality	2	pc		
		Total Direct Cost			
		Total Indirect Cost			
		Total Taxes			
		Total Contract Cost			

Prepared by:

 Signature over printed name

Name of company: _____

Date signed: _____