PROJECT : DESIGN AND DEVELOPMENT OF MECHANICAL PINEAPPLE LEAF SCRAPER

BILL OF MATERIALS/COST ESTIMATES

		PARTICULARS	QUANTITY	UNIT	UNIT PRICE	AMOUNT
I. F	ABRI	CATION OF MAIN FRAME, SLIDER ASSY & SCRAP	ER ASSY.			
		Tubular, 1"X 1" x 1.2mm, MS	7	length		
		Flat bar, 1 1/2" X 1/4", MS	2	рс		
		Flat bar, 2"X1/4", MS	2	рс		
		Stud bolt M12x1m, ordinary	1	length		
		Allen type screw, M12x 150mmL, stainless steel	6	set		
		Allen type screw, M6x38mmL, with nuts and washer, stainless steel	20	set		
		Hexagonal bolt and nut and lock washer, M12 x 1-1/2" high tensile	30	set		
		Nuts and flat washer for M12 bolt	60	pcs		
		Ball bearing, 6201, japan	16	pcs		
		Bushings, OD: 25, ID: 12, 50mmL	5	pcs		
		Flat bar, 1 1/2" X 1/4", SS (Scraper blade)	2	m		
		Cut-off wheel, 4"dia	10	pcs		
		Grinding disc, 4"dia	10	pcs		
		Welding electrode, 3/32, assorted	3	kg		
		Step drill bit, 4-32mm	3	pcs		
		Drill bit, 12mm dia., metal	3	pcs		
		Drill bit, 10mm dia., metal	3	pcs		
		Drill bit, 6mm dia., metal	4	pcs		
		Drill bit, 5mm dia., metal	4	pcs		
		Compression spring, 4mm dia. rod	1	set		
		-				
II. I	FABR	ICATION OF PINEAPPLE LEAVES FLATFORM				
		Good Lumber, 2" X 8'X10', S4S, Hard wood	1	pcs		
		Pineapple leaf lock assy.	1	assy		
		11		,		
III.	TRA	NSMISSION ASSY.				
		1500W, 48-60V, BLDC / E bike electric motor, high torque, with controller, botton controls for direction of rotation, heavy duty	1	lot		
		Roller chains # 40	7	m		
		Sprockets, 40B32	2	рс		
		Idlers sprockets, 40B	2	рс		
		CRS shaft, 1" dia. X 3m	1	pc		
IV.	FINIS	SHING WORKS		_		
		Epoxy primer, gray	1	gal		
		Lacquer thinner	1	gal		
		Sand paper, assorted	30	pcs		
		Glossy enamel paint, quick dry, green	1	gal		
		Paint thinner	1	gal		
		Rugs	3	kg		
		Body filler,	1	l		

PARTICULARS	QUANTITY	UNIT	UNIT PRICE	AMOUNT
Vinyl sticker, 150mmX150mm, philfida logo	4	pcs		
PhilFIDA sticker, vinyl waterproof, 3"x3"	1	рс		
DELIVERY/MODIFICATION				
Modification and adjustments after testing	1	lot		
Delivery at Fiber Processing and Utilization	4			
Laboratory, Visayas Avenue, Vasra Quezon City	1	lot		
a. Total Material Cost b. Total Labor Cost c. Total Direct Cost (a+ b)				
d. Total Indirect Cost e. Taxes (12%) f. Total Contract Cost (c+d+e) Submitted by:				
d. Total Indirect Cost e. Taxes (12%) f. Total Contract Cost (c+d+e)	_			
d. Total Indirect Cost e. Taxes (12%) f. Total Contract Cost (c+d+e) Submitted by:	_			