



Republic of the Philippines
Department of Agriculture
PHILIPPINE FIBER INDUSTRY DEVELOPMENT AUTHORITY
Regional Office V

Bicol University Compound, Legazpi City 4500
Email: fida_rov@yahoo.com / rolegaspi@philfida.da.gov.ph
Website: www.philfida.da.gov.ph / Tel. No. 052-742-1511

REQUEST FOR QUOTATION
RFQ No. 001-2025B

The Philippine Fiber Industry Development Authority (PhilFIDA) Regional Office V, thru its Bids and Awards Committee (BAC), invites all suppliers/contractors to send their sealed price quotations, within four (4) calendar days from publication hereof, for the civil works described as follows:

Item No.	Description of Items	Approved Budget (Php)	Place of Delivery
One (1) Lot	<p>Provision of Labor and Materials for the repair of Abaca Tuxy Buying Special Project Facility in Paniqui, Caramoran, Catanduanes with the following Program of Works:</p> <ol style="list-style-type: none"> 1. Landslide Remediation - removal of landslide debris at least 7 meters from the closest structure, at least 0.2 meter below the finish floorline of the trading/office, clearing and cleaning in and around the trading center and warehouse center. 2. Ceiling works- repair of the ceiling in the trading center and stripping center 3. Painting works - repainting works in the trading center and stripping center and interior primer painting in the warehouse building 4. Electrical Works - repair/replacement of damaged electricals 5. Roof Works - repair of roofs and replacement of corner flushing 6. Maintenance and Repainting of Machines - replacement of coil springs, repainting and lubrication of machines 7. Signage Installation - placement of new project signage 8. Window Replacement - replacement of one window in the trading center <p><i>(Please quote on the attached detailed labor and materials requirement per work component).</i></p>	945,492.47	Paniqui, Caramoran, Catanduanes

Please quote your best offer for the civil works described above. Submit your sealed quotation duly signed by you or your duly authorized representative not later than 5:00 P.M. of February 18, 2025. Award of the contract shall be made to the lowest and responsive quotation which complies with the minimum requirements as stated in the RFQ and Program of Work/Bill of Quantities. A clear copy of your **2025 Mayor's/Business Permit, PhilGEPS Certificate of Registration, PCAB License, and Income/Business Tax Return** are also required to be submitted along with your sealed quotation. Quotations can be submitted manually at the address indicated below or emailed to bac.fidarov@gmail.com.

The BAC Secretariat
Philippine Fiber Industry Development Authority
Regional Office V
Bicol University Compound, Legazpi City

For clarification, you may contact Mr. George P. Olayres, BAC Secretariat at telephone number (052) 742-1511.

MARLON F. REBANCOS
Chairperson, BAC
Date: February 11, 2025

INSTRUCTIONS:

1. Accomplish this RFQ correctly and accurately
2. Do not alter the contents of this form in any way
3. Technical specifications with an asterisk (*) are mandatory. Failure to comply with any of the mandatory requirements will disqualify your quotation
4. Failure to follow these instructions will disqualify your entire quotation

PR Number: JO-ATBSP-2025B-01

Date: _____

MARLON F. REBANCOS

Chairperson, Bids and Awards Committee
PhilFIDA Regional Office V
Bicol University Compound, Legazpi City

Sir:

After having carefully read and accepted the terms and conditions in the Request for Quotation, hereunder is our quotation/s for the item/s as follows:

Item Number	Description of Item	Contract Cost (Php)
One (1) Lot	Provision of Labor and Materials for the repair of Abaca Tuxy Buying Special Project Facility in Paniqui, Caramoran, Catanduanes with the following Program of Works: <ol style="list-style-type: none">1. Landslide Remediation - removal of landslide debris at least 7 meters from the closest structure, at least 0.2 meter below the finish floorline of the trading/office, clearing and cleaning in and around the trading center and warehouse center.2. Ceiling works- repair of ceiling in the trading center and stripping center3. Painting works - repainting works in the trading center and stripping center and interior primer painting in the warehouse building4. Electrical Works - repair/replacement of damaged electricals5. Roof Works - repair of roofs and replacement of corner flushing6. Maintenance and Repainting of Machines - replacement of coil springs, repainting and lubrication of machines7. Signage Installation - placement of new project signage8. Window Replacement - replacement of one window in the trading center <i>(Please quote on the attached detailed labor and materials requirement per work component).</i>	

Total Amount:* _____

Amount in Words:* _____

The above-quoted price is inclusive of all costs and applicable taxes. Prices indicated are valid until _____.

Very truly yours,

Name and Signature of Representative*

Name of Company*

Address*

Contact Number



Republic of the Philippines
 Department of Agriculture
PHILIPPINE FIBER INDUSTRY DEVELOPMENT AUTHORITY
 3/F DA-PCAF Bldg., Department of Agriculture, Elliptical Rd., Diliman, Quezon City
 Email: oed@philfida.da.gov.ph, Website: www.philfida.da.gov.ph
 Trunk line: 928-8756 Local 2681; Tel/Fax: 441-4606

NAME/LOCATION OF PROJECT:	Appropriation:
REHABILITATION OF ATBSP FACILITY Brgy. Panique, Caramoran, Catanduanes	Source of Funds:
PROJECT DESCRIPTION:	Target Start Date:
The project focuses on the rehabilitation of the ATBSP facilities, located in the municipality of Caramoran, Catanduanes. These facilities were significantly damaged by the combined effects of Typhoon Kristine and Super Typhoon Pepito, which caused structural damage to the roof, ceiling, and paintwork. The rehabilitation efforts will restore these centers to full functionality, ensuring they meet operational standards.	Total Project Duration: 60 C.D

ESTIMATED COST OF PROPOSED WORK

Project Component Description	% Total	Estimated Direct Cost	Total Mark-up	VAT	Total Cost
A. Landslide Remediation			%		
I. Earthworks, Clearing and Cleaning of Trading and Office Center	33.46%				
B. Rehabilitation			%		
I. Removal of Existing Structure (damaged ceiling)	0.74%				
II. Ceiling Works (Repair)	16.73%				
III. Painting Works (Repainting of Trading Center and Stripping Center Office)	37.67%				
IV. Electrical Works (Repair)	1.53%				
V. Roof Works (Corner Flushing)	1.01%				
VI. Maintenance and Repainting of Machines	5.29%				
VII. Signage Installation	2.58%				
VIII. Window Installation	0.99%				
TOTAL	100.00%				

Name and Signature of Representative*

Name of Company*

Address*

Contact Number



BILL OF QUANTITIES

Item Description : Earthworks, Clearing and Cleaning of Trading and Office Center					
Unit of Measurement					
Output per Day					
Estimated Quantity					
	Designation	No. Of Person/s	No. of Hours	Hourly rates	Amount (Php)
A.	Skilled Operator	2	24		
	Laborer	10	80		
	Sub-Total for A				
	Name and Capacity	No. of Unit/s	No. of Hours	Hourly Rates	Amount (Php)
B.	Equipment				
	a. Back hoe (including Mobilization and Demobilization)	1	24		
	b. Loader (Including Mobilization and Demobilization)	1	24		
	c. MiniDump Truck (3.5cu.m.	1	24		
	Minor Tools (10% Labor Cost)				
	Sub-Total for B				
C	Total (A+B)				
D	Direct Cost				
E	Indirect Cost (17%)				
F	Value Added Tax (7%)				
G	Total Unit Cost				

Item Description: Removal of Existing Structure (Damaged Ceiling)					
Unit of Measurement:					
Output per Day:					
Estimated Quantity:					
	Designation	No. Of Person/s	No. of Hours	Hourly rates	Amount (Php)
A	Laborer	4	16		
B	Direct Cost				
C	Indirect Cost (17%)				
D	Value Added Tax (7%)				
E	Sub-Total for A				

Item Description : Ceiling Works					
Unit of Measurement					
Output per Day					
Estimated Quantity					
	Designation	No. Of Person/s	No. of Hours	Hourly rates	Amount (Php)
A.	Skilled Laborer	4	72		
	Laborer	2	72		
	Sub-Total for A				
B.	Name and Specification	Unit	Quantity	Unit Cost	Amount (Php)
	Equipment				
	Scaffolding H-Frame Set w/ Cat	set	4		
	Sub-Total for B	pcs			
C.	Materials				
	0.5mm x 5m Metal Furring	pcs	80		
	0.6mm x 5m C-Channel	pcs	24		
	0.5mmX 1" x 5m Wall Angle	pcs	30		
	0.8mm W-Clip	pcs	600		
	1/4" Plywood	pcs	45		
	5/32 x 1/2 Blind Rivets	box	8		
	1" Concrete Nail	kl	1		
	Sub-Total for C				
E	Direct Cost (A+B+C)				
E	Indirect Cost (17%)				
F	Value Added Tax (7%)				
G	Total Unit Cost				

Item Description : Painting Works (Repainting of Trading Center and Stripping Center Office)					
Unit of Measurement					
Output per Day: 8.0 sqm per day					
Estimated Quantity: 732.7					
	Designation	No. Of Person/s	No. of Hours	Rate per day	Amount (Php)
A.	Painter	12	12		
	Sub-Total for A				
B.	Name and Specification	No. of Sets	Quantity	Unit Cost	Amount
	Equipment				
	Scaffolding H-Frame Set w/ catwalk	12	12		
	Sub-Total for B				
C.	Name and Specification	Unit	Quantity	Unit Cost	Amount (Php)
	Materials				
	Skim Coat (ceiling)	bag	8		
	Mesh Tape	pcs	4		
	Flat Latex White	pail	10		
	Gloss Latex White	pail	14		
	Elastomeric Paint (Interior &	pail	3		
	18" Roll Brush Set	set	4		
	4" Roll Brush Set	set	3		
	Paint Brush (Various)	pcs	6		
	Sanding Paper	pcs	10		
	Wood Varnish	lit	2		
	Total for C				
D	Total (A+B+C)				
E	Direct Cost				
F	Indirect Cost (17%)				
G	Value Added Tax (7%)				
H	Total Unit Cost				

Item Description : Electrical Works					
Unit of Measurement					
Output per Day:					
Estimated Quantity:					
	Designation	No. Of Person/s	No. of Hours	Hourly rates	Amount (Php)
A.	Skilled Laborer	1	16		
	Sub-Total for A				
	Name and Specification	Unit	Quantity	Unit Cost	Amount (Php)
B.	Materials				
	9watts Downlight	pcs	13		
	15watts Downlight	pcs	6		
	Total for B				
C	Total (A+B+C)				
D	Direct Cost (A+B)				
E	Indirect Cost (17%)				
F	Value Added Tax (7%)				
G	Total Unit Cost				

Item Description : Roof Works (Corner Flushing)					
Unit of Measurement					
Output per Day:					
Estimated Quantity:					
	Designation	No. Of Person/s	No. of Hours	Hourly rates	Amount (Php)
A.	Skilled Laborer	1	16		
	Unskilled Laborer	1	16		
	Sub-Total for A				
	Name and Specification	Unit	Quantity	Unit Cost	Amount (Php)
B.	Materials				
	1.0mm Pre-Painted Corner Flushing	pcs	10		
	Black Screw 2.0mm x 35mm	pack	1		
	Total for B				
C	Direct Cost (A+B)				
D	Indirect Cost (17%)				
E	Value Added Tax (7%)				
F	Total Unit Cost				

Item Description : Maintenance and Repainting of Machines					
Unit of Measurement					
Output per Day:					
Estimated Quantity:					
	Designation	No. Of Person/s	Unit	Rate (man-day)	Amount (Php)
A.	Skilled Laborer	10	man-day		
	Sub-Total for A				
B.	Materials	QTY	Unit	Unit Price	Total
	Enamel Paint (green)	10	Gal		
	Paint Brush 4"	10	pcs		
	Steel Brush	10	pcs		
	WD-40 Penetrating Oil (12.9 oz)	7	pcs		
	Deisel Oil	2	li		
	Multi Purpose grease (500 g)	5	can		
	Coil Spring	5	pcs		
	Sand Paper (Grit 400)	30	sheets		
	Grease gun	2	pcs		
	Sub-Total for B				
	C.	Direct Cost (A+B)			
D.	Indirect Cost (17%)				
E.	Taxes (7%)				
F.				TOTAL	

Item Description : Signage Installation					
Unit of Measurement					
Output per Day					
Estimated Quantity					
	Designation	No. Of Person/s	No. of Hours	Hourly rates	Amount (Php)
A.	Skilled Laborer	1	24		
	Laborer	1	24		
	Sub-Total for A				
	Name and Specification	Unit	Quantity	Unit Cost	Amount (Php)
B.	Materials				
	2" Ø G.I. Pipe (will be provided by the end user)	pcs	3		
	G.I. Plain Sheet G.A. 18 4ft x 8ft	pcs	1		
	Flat Bar 1" x 1/4"	pcs	2		
	Paint Brush 2"	pcs	3		
	Concrete(Cement)	cu. M.	0.1		
	Angle Bar 2" x 2"	pcs	1		
	Welding Rod	box	1		
	Primer	lit	1		
	Paint(White for Post & Frame)	lit	1		
	Paint (Green for G.I. Sheet Framing)	lit	1		
	Paint Thinner	lit	1		
	Vinyl Sticker (1.6m x 0.8m)	lot	1		
	Sub-Total for B				
C	Total (A+B)				
D	Direct Cost				
E	Indirect Cost (17%)				
F	Value Added Tax (7%)				
G	Total Unit Cost				

Item Description : Window Installation					
Unit of Measurement					
Output per Day:					
Estimated Quantity:					
	Designation	No. Of Person/s	No. of Hours	Rate (man-day)	Amount (Php)
A.	Skilled Laborer	1	man-day		
	Sub-Total for A				
B.	Name and Specification	Unit	Quantity	Unit Cost	Amount (Php)
	Materials				
	Aluminum Sliding Window	set	1		
	Total for B				
C	Direct Cost (A+B)				
D	Indirect Cost (17%)				
E	Value Added Tax (7%)				
F	Total Unit Cost				

Name and Signature of Representative*

Name of Company*

Address*

Contact Number