

PROJECT : REPAIR OF SHED FOR FPUL 15kVA GENSET  
 OWNER : PHILIPPINE FIBER INDUSTRY DEVELOPMENT AUTHORITY  
 LOCATION : FPUL, BAI COMPOUND, VISAYAS AVENUE, VASRA, QUEZON CITY

#### QUOTATION

PARTICULARS			QUANTITY	UNIT	UNIT PRICE	AMOUNT
<b>I. AREA CLEARING, EXCAVATION AND DEMOLITION WORKS</b>			<b>1</b>	lot		
<b>II. DISMANTLING AND REINSTALLATION OF EXISTING ELECTRICAL WIRINGS FOR GENSET</b>			<b>1</b>	lot		
<b>III. FABRICATION WORKS OF SHED</b>						
		2" X 3" X 1.2mm C-purlins	4	pcs		
		2" X 2" X 1.2mm Tubular	3	pcs		
		Corrugated roof sheet, gauge 26, pre-painted (0.95m x 12')	4	pcs		
		8' Ridge roll, pre-painted	1	pcs		
		2" Gl. Pipe, schedule 40	4	pcs		
		Gl. Steel matting, 2" x 6mm rod	1	pc		
		Angle bar, 2x2x1/4"	1	pc		
		Rebar, 12mm ø	1	pc		
		Tex screw	180	pcs		
		Welding rod 6013	5	kg		
		Paint rollers 4"	4	pcs		
		Metal cutting disc, 4"	5	pcs		
		Metal Grinding disc, 4"	5	pcs		
		Cement	3	bags		
		Sand	6	bags		
		Epoxy primer	3	gal		
		Laquer Thinner	1	gal		
<b>IV. DISPOSAL OF CONSTRUCTION WASTE MATERIALS</b>			<b>1</b>	lot		
			<b>Total Direct Cost</b>			
			<b>Total Indirect Cost</b>			
			<b>Total Taxes</b>			
			<b>Total Contract Cost</b>			

Prepared by:

Name and Signature of Contractor

Company Name:

Date: